

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

JUL 1 1963

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cooperative Refining Assn 15-051-05396-00-00

Complete Address: Drawer (C) Great Bend, Kansas

Lease Name Giebler Well No. 3

Location NE SW SE Sec. 27 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3850

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling & Globe Cementing Co

Address: Great Bend, Kansas License No. _____

Operation Completed: Hour 6PM Day 22 Month 6 Year 63

The Above well was plugged as follows:

8 5/8" 255' circulated with cement - 5 1/2" 3850' with 175 sax cement -
5 1/2" squeezed in Dakota section with 250 sax cement approx 800' -
no pipe recovery.

Pumped 30 sax gel followed by plug and 20 sax cement - pumped plug to
750' - shot 5 1/2" at 500' - pumped 23 sax gel, filling hole and circulating
gel to surface between 8 5/8" & 5 1/2" - mud to 80', cement 80' to bottom
cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/1/63
INV. NO. 4335-W

Signed: [Signature]
Well Plugging Supervisor