

 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

DEC 14 1967
12-13-67

Operator's Full Name Dane G. Hansen Trust 15.051.20176.00.00

Complete Address: Logan, Kansas 67646

Lease Name Storm "B" Well No. 2

Location S/2 SE NE Sec. 34 Twp. 13 Rge. 20 (E) (W) X

County Ellis Total Depth 3863

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: C & G Drlg. Co.

Address: Wichita, Ks. License No.

Operation Completed: Hour 1 P Day 11 Month 12 Year 1967

The Above well was plugged as follows:

RTD 3863' 8 5/8 csg set at 207' cwc 140 sc.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 210' set cementing plug and displace 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 12/13/67
INV. NO. 6896-W