

Y KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 - 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dane G. Hansen Trust 15-051-2020 3:00:00

Complete Address: Logan, Kansas

Lease Name Leo Storm "D" Well No. 1

Location SE NE NE Sec. 34 Twp. 13 Rge. 20 (E) X (W) X

County Ellis Total Depth 3902

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: C - G Drlg. Co.

Address: Wichita, Ks. License No. _____

Operation Completed: Hour 9:45 P Day 1 Month 2 Year 1968

The Above well was plugged as follows:

RTD 3902' 8 5/8 csg set at 204 cwc 140 sc. Cem. Mat. 100 sc cem. W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/5/68
INV. NO. 7205-U

Signed: Russ F. Dunsen
Well Plugging Supervisor