

Y KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 9 1964  
03-09-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Terrel Drg Co 15-051-19021-00-00  
Complete Address: Russell, Kansas  
Lease Name Nicholson Well No. 1  
Location NE NE SW Sec. 34 Twp. 13 Rge. (E) (W) 20  
County Ellis Total Depth 3860  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Halliburton Cementing Co  
Address: Hays, Kans License No.       
Operation Completed: Hour 2PM Day 28 Month 2 Year 64

The Above well was plugged as follows:

8 5/8" 200' circulated with cement - 5 1/8" 3850' with 75 sax cement -  
5 1/8" squeezed at 908 with 250 sax cement and 200 sax cement - 450 sax total -  
no pipe recovery.

Pumped hole full heavy gel mud ( 35 sax Gel), pumped wiper plug followed  
by 70 sax cement - cement 560' to 0' - pump pressure 800#

Mudding and cementing by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edna Terry*  
Well Plugging Supervisor

3/11/64  
8443-U