

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1968
CONSERVATION DIVISION
Wichita, Kansas

15:051-20230-00-00

Operator's Full Name Birmingham-Bartlett Drilling Company

Complete Address: 300 Kaufman Bldg., Wichita, Kansas 67202

Lease Name Nicholson "C" Well No. 1

Location SE NW NW Sec. 34 Twp. 13 Rge. 20 (E) (W) XX

County Ellis Total Depth 3856

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith Pipe Pulling

Address: 20 1/2 E 6th Ellinwood, Kansas License No. 396

Operation Completed: Hour 12 N Day 8 Month 12 Year 1968

The Above well was plugged as follows:

Total Depth 3856' 8 5/8 csg set at 227' cwc 165 sc.

4 1/2 csg set at 3849' cw 150 sc cmt.

Filled 4 1/2 csg W/sd (3840-56) Dumped 3 sc cmt. W/dump bailer. (3805-40).

Cutoff and recovered 2916' of 4 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sc gel W/4 sc hulls, 120 sc 50-50 poz 6%;

5 sc gelW/1 sc hulls, plug and 10 sc cmt. to surface.

(0-40) Cmt. (40-200) Gel (200-720) Cmt. (720-TD) Gel.

I hereby certify that the above well was plugged as herein stated.

INDEXED
DATE 12/9/68
INV. NO. 8961-4

Signed: Geo. F. Massey
Well Plugging Supervisor