

KANSAS

Form CP-3
Rev. 6-4-68

P

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

STATE CORPORATION COMMISSION
APR 15 1978
04-14-78

API Number 15 - 051 - 21121 - 66 - 00 (of this well)

Operator's Full Name Lario Oil & Gas Co.

Complete Address 301 South Market St. Wichita, Kansas 67202

Lease Name Younger Well No. 9

Location SW SW NE Sec. 25 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3865'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 3 P Day 12 Month 4 Year 1978

The above well was plugged as follows:

Total Depth 3865' 8 5/8 csg set 306' cwc 225 sk.

5 1/2 csg set 3863' W/150 sk cem.

5 1/2 csg FBTD 3785' with top perf. (3632')

Filled 5 1/2 csg W/sd (3785'-3600') dumped 4 sk cem. W/dump bailer. (3600'-3570')

Cutoff & recovered 3034' of 5 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water

W/100 lbs hulls -followed with 70 sk 50-50 poz 2% -displaced with 10 sk gel &

water -capped with cementing plug & 70 sk 50-50 poz & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Murray
Well Plugging Supervisor

DATE 4-14-78

INV. NO. 7111-2