

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 30 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Lario Oil & Gas 15051-02887-00-00

Complete Address: 501 S Market Wichita, Kansas

Lease Name Younger Well No. 8

Location NW SW NE Sec. 25 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 5802

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 596

Operation Completed: Hour 7PM Day 25 Month 6 Year 64

The Above well was plugged as follows:

8 5/8" 249' circulated with cement - 5 1/2" 5795' with 150 sax cement.
Filled with sand to 5780', set 4 sax cement with dump bailer.
pulled 2690' 5 1/2" to 600' - pumped 15 sax gel mud and spotted
20 sax cement through 5 1/2" at 600' - pulled 5 1/2" to 200', circulated
hole with gel mud (12 Sax) displaced 20 sax cement through
5 1/2" at 200', heavy mud to 55', set bridge and 10 sax cement
to bottom cellar.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 6/30/64
INV. NO. 9392-W