

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 4 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Lario Oil & Gas Company 15-051-02882-00-00

Complete Address 301 South Market, Wichita, Kansas 67202

Lease Name Younger Well No. 3

Location SW SW SE Sec. 25 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3845'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Nicholas Pipe Pulling

Address Geneseo, Kansas License No. 711

Operation Completed: Hour 3:30 P. Day 2 Month 4 Year 1974

The above well was plugged as follows:

Total Depth 3845' 8 5/8 csg set at 200' cwc 150 sk.

5 1/2 csg 3843' cw 125 sk cem.

5 1/2 csg PBSD 3800' with top perf. (3659')

Set 5 1/2 wood plug at 3500' -poured 20' sand -dumped 4 sk cem W/dump bailer. (3450-3500)

Cutoff and recovered 1985' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water -100 lbs hulls -70 sk cem. -8 sk gel

& water -released 8 5/8 plug and pumped 50 sk cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. J. Massey
Well Plugging Supervisor

PAY TO THE ORDER OF THE
STATE TREASURER
TO: STATE OF KANSAS
FOR 4/4/74
STATE COL. ISSION
INV. NO. 8882-W
Conservation Division