

KANSAS

12
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 26 1973
7-26-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Cameran K. Reed 15-051-20191-00-00

Complete Address Box 13262 Kansas City, Mo.

Lease Name Storm "C" Well No. 1

Location SW NW NW Sec. 35 Twp. 13 Rge. (E) (W) 20

County Ellis Total Depth 3862'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 3:45 P Day 13 Month 7 Year 1973

The above well was plugged as follows:

Total Depth 3862' 8 5/8 csg set at 209' cwc 140 sk.

4 1/2 csg set at 3850' cw 125 sk cmt.

4 1/2 csg squeezed from 850'-1200' with 500 sk cmt & circ. to surface.

Ran 95 jts tbg set at 2945' --circ. 20 sk gel & water W/200 lbs hulls--displaced

40 sk cmt. (2360-2945). Pulled tbg to 1525' & displaced 20 sk cmt. (1230-1525)

Pulled tbg to 600' & circ. 60 sk cmt to base of cellar. Pulled remaining tbg &

capped 4 1/2 csg with 5 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Z. Masany
Well Plugging Supervisor

INDEXED
DATE 7/24/73
REV. NO. 7670-11