

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6568
Name: Kaiser-Francis Oil Company
Address 1: P.O. Box 21468
Address 2: _____
City: Tulsa State: OK Zip: 74121 + 1468
Contact Person: Charlotte Van Valkenbyrg
Phone: (918) 491-4314
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Lansing Depth to Top: 3204' Bottom: 3250' T.D. 3362'
Topeka Depth to Top: 3092' Bottom: 3120' T.D. PB-3127'
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 129-10007 00 00
Spot Description: _____
C NW, NW, SE Sec. 29 Twp. 32 S. R. 43 East West
330 2310 Feet from North / South Line of Section
330 2310 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Morton
Lease Name: Mohler Well #: 1
Date Well Completed: 7/31/1954
The plugging proposal was approved on: 4/7/2010 (Date)
by: Jack Maclaskey (KCC District Agent's Name)
Plugging Commenced: 4/8/2010
Plugging Completed: 4/9/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Lansing	Gas	Surface	8 5/8"	681'	None
Topeka	Gas	Production	5 1/2"	3358'	742'

RECEIVED
MAY 14 2010
5-14-10
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tbg @ 3100', Pump 40 sks Class "C" cement w/ 100 lbs cottonseed hulls (3100' - 2716') POH w/ tbg . Tag TOC @ 2683' . Cut & pull 5 1/2" casing from 742' , POH w/ 20 jts casing. Run tbg @ 1410' & spot 40 sks cement up to 1015' . Pull tbg up to 731' , mix & pump 50 sks Class "C" cement up to 547' , Pull tbg up to 350' & spot 30 sks cement up to 250' , POH w/ tbg & top out 34' - 4' w/ 15 sks cement.

DR

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc.
Address 1: P.O. Box 1706 Address 2: _____
City: Duncan State: OK Zip: 73534 + 1706
Phone: (580) 467-0258
Name of Party Responsible for Plugging Fees: Kaiser-Francis Oil Company
State of Oklahoma County, Tulsa , ss.
Charlotte Van Valkenbyrg Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct. So help me God.

Signature: C. Van Valkenbyrg