

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5003
Name: McCoy Petroleum Corporation
Address 1: 8080 E. Central, Suite #300
Address 2:
City: Wichita State: KS Zip: 67206-2366
Contact Person: Brent Reinhardt
Phone: 316-636-2737
Type of Well (Check One): Oil Well Gas Well O&G D&A Cathodic
 Water Supply Well Other: SWD Permit #:
 ENHR Permit #: Gas Storage Permit #:
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Oread Depth to Top: 3888 Bottom: 3892 T.D. 4733'
Cherokee Depth to Top: 4700 Bottom: 4705 T.D. 4733'
Mississippian Depth to Top: 4713 Bottom: 4730 T.D. 4733'

API Number 15-047-21526 0001
Spot Description: E2-NW-NW Sec 20 Twp 26 S. Rng. 18 East West
660 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Edwards
Lease Name: STURGEON "A" #1-20
Date Well Completed: 1/11/07
The plugging proposal was approved on: 5/3/10 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 5/10/10
Plugging Completed: 5/11/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	356'	0
		Production	4 1/2"	4763'	2650'

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 19 2010
5-19-10
CONSERVATION
WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

5/11/10: MIRU. Pumped 25 sacks cement with 150# hulls and displaced to 3780'. Cement was at 3780'. Ripped casing at 2650' and pipe came free. Pulled casing up to 1280'. Pumped 50 sacks, 15 gel, with 100# hulls. Pulled to 390'. Pumped 50 sacks with 100# hulls. Pulled to 40'. Pumped 25 sacks cement to surface.

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.
Address 1: 190th US 56 Highway Address 2:
City: Ellinwood, State: KS Zip: 67526
Phone: 620-727-3410

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation
State of Kansas County, Sedgwick, ss.

Scott Hampel Employee of Operator or Operator on above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
(Signature) Scott Hampel