

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31569
Name: Bach Oil Production
Address 1: P.O. Box 723
Address 2: _____
City: Alma State: NE Zip: 68920 + _____
Contact Person: Jason Bach
Phone: (78/5) 476-5254
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 3270 Bottom: 3385 T.D. 3529
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 163-21185 00 00
Spot Description: _____
C SW NE NE Sec. 6 Twp. 6 S. R. 20 East West
4,290 Feet from North / South Line of Section
990 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rooks
Lease Name: McClurg Well #: 2
Date Well Completed: 1/29/1981
The plugging proposal was approved on: 4/29/2010 (Date)
by: Bruce Basys (KCC District Agent's Name)
Plugging Commenced: 5/7/2010
Plugging Completed: 5/7/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	334	
		Production	4 1/2	3529	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tubing ran to 1670', spot 110 sx cement with 330# hulls, cement did circulate.
Pulled tubing to 840', cement to surface with 55sx & 200# hulls.
Pulled all tubing & topped of with 5sx cement, casing stayed full.
8 5/8, pumped 10sx cement, presure to 200 lbs. and shut in.

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 27 2010
CONSERVATION DIVISION
WICHITA, KS

Plugging Contractor License #: _____ Name: Allied Cementing co.
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: Kansas Zip: 67665 + _____
Phone: (758) 483-2627
Name of Party Responsible for Plugging Fees: Jason Bach
State of Nebraska County, Harlan, ss.

Dale Ferland (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dale Ferland