

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 31569 Name: Bach Oil Production Address 1: P.O. Box 723 Address 2: City: Alma State: NE Zip: 68920 Contact Person: Jason Bach Phone: (785) 476-5254 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: 3382 Bottom: 3642 T.D. 3642

API No. 15 - 163-23174 00 00 Spot Description: NW NW Sec. 16 Twp. 7 S. R. 20 East West 4,290 Feet from North / South Line of Section 4,620 Feet from East Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Rooks Lease Name: Risley B Well #: 3 Date Well Completed: July 22, 1991 The plugging proposal was approved on: 11/17/2009 (Date) by: Richard Williams (KCC District Agent's Name) Plugging Commenced: 5/10/2010 Plugging Completed: 5/10/2010

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows include Surface (8 5/8, 257) and Production (4 1/2, 3631).

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tubing ran to 2004', spot 100 sx cement with 200# hulls. Pulled tubing to 1500', cement with 100sx & 100# hulls. Pulled tubing to 900', pumped 50sx cement & 150# hulls, cement did circulate. Pulled all tubing & topped off with 30sx cement. 5/13/2010, topped off 4 1/2 w/ 10sx cement, could only pump 5sx cement down 8 5/8.

RECEIVED KANSAS CORPORATION COMMISSION MAY 27 2010 CONSERVATION DIVISION WICHITA, KS

Plugging Contractor License #: 99996 Name: Allied Cementing co. Address 1: P.O. Box 31 Address 2: City: Russell State: Kansas Zip: 67665 Phone: (758) 483-2627

Name of Party Responsible for Plugging Fees: Jason Bach State of Nebraska County, Harlan, ss. Dale Ferland (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dale Ferland