

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
Must be Filled

OPERATOR: License #: 4058
Name: American Warrior
Address 1: P.O. Box 399
Address 2: _____
City: Garden City State: KS Zip: 67846 + _____
Contact Person: Kevin Wiles
Phone: (620) 275-2963
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: D-27,773
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: 4842 Bottom: 4851 T.D. 6225
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15-033-00028-00-02
Spot Description: C-NE-NE-SW
C NE-NE-SW Sec. 17 Twp. 33 S. R. 18 East West
2,319 Feet from North / South Line of Section
2,335 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Comanche
Lease Name: Hackney Well #: #1 SWD
Date Well Completed: 8/18/1966
The plugging proposal was approved on: 4/22/2010 (Date)
by: Richard Lacey (KCC District Agent's Name)
Plugging Commenced: 04/22/2010
Plugging Completed: 04/27/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Conductor	13 3/8	261	None
		Surface	8 5/8	2667	None
		Production	5 1/2	5245	3500

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 4680', 2sx cement on CIBP, cut casing at 3500', lay down, run tubing to 1st 990', pump 20 sx gel, 50sx 60/40 poz 2% gel, 2nd 290', 50sx 60/40 poz, 3rd 60', 20sx 60/40 poz, circulate to surface 5/11 - Measure down surface, cement at 20', measure conductor, cement down 6', back fill cellar

RECEIVED
MAY 17 2010

Plugging Contractor License #: 5105 Name: Clarke Corporation **KCC WICHITA**
Address 1: P.O. Box 187 Address 2: 107 W. Fowler
City: Medicine Lodge State: Kansas Zip: 67104 + _____
Phone: (620) 886-5665
Name of Party Responsible for Plugging Fees: American Warrior
State of Kansas County, Barber, ss.

Mark Morgenstern Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Morgenstern