

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5447
Name: Oxy USA, Inc
Address 1: P.O. Box 2528
Address 2: _____
City: Liberal State: KS Zip: 67905
Contact Person: Kenny Andrews
Phone: (620) 629 4200
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Morrow Depth to Top: 5328 Bottom: 5286 T.D. 5468
Chase Depth to Top: 2554 Bottom: 2674 T.D. A
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 081-20257 00 02
Spot Description: SW NW
SW NW Sec. 7 Twp. 29 S. R. 33 East West
1980 Feet from North / South Line of Section
660 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Haskell
Lease Name: Unruh B Well #: 3
Date Well Completed: 6-23-82
The plugging proposal was approved on: 12-16-09 (Date)
by: Mike Meier (KCC District Agent's Name)
Plugging Commenced: 12-17-09
Plugging Completed: 12-17-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			21	40	—
			8 5/8	1820	—
			5 1/2	5459	1401 (TOC 1500)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP + 2 sx cmt from 2475 to 2460, Shot loose-circ. hole w/mud + mixed 50 sx plug 1400 to 1250 40 sx 700 to 580 10 sx 40 to 0. Capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc.
Address 1: Rt 1 Box 49 BA Address 2: _____
City: Tyrone State: OK Zip: 73951 + 9731
Phone: (580) 854 6515

Name of Party Responsible for Plugging Fees: Oxy USA, Inc. 1701 N Kansas Rd Box 2528 Liberal, KS. 67905
State of Kansas County: Seward
Kenny Andrews (Print Name) Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is true and correct, and the same are true and correct, so help me God.

Signature: Kenny Andrews

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
APR 01 2010
4-1-10
CONSERVATION DIVISION
WICHITA, KS



OXY USA Inc.
1701 N. Kansas, Liberal, KS 67901
P.O. Box 2528, Liberal, KS 67905-2528

March 29, 2010

Kansas Corporation Commission
Wichita State Office Bldg.
130 South Market, Room 2078
Wichita, Kansas 67202

OXY USA Inc.
Re: Well Plugging Record (CP-4)
Re: Closure of Surface Pond (CDP-4)

Unruh B-3
API # 15-081-20257
Section 7-29S-33W NW/4
Haskell, Co. Ks.

To Whom It May Concern:

Please find enclosed the Well Plugging Record (CP-4) for the subject well. Also, please find the pit closure form (CDP-4).
Thanks for your help.

If there are any questions or you require further information, please contact me at the above address or by Phone at (620) 629 - 4232.

Sincerely,

A handwritten signature in black ink, appearing to read 'Kenny L. Andrews', written in a cursive style.

Kenny L. Andrews
Well Operations Lead
OXY USA Inc.
Hugoton Asset
Liberal, Kansas

RECEIVED
KANSAS CORPORATION COMMISSION
APR 01 2010
CONSERVATION DIVISION
WICHITA, KS