

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5278  
Name: EOG Resources, Inc.  
Address 1: 3817 NW Expressway ; Suite 500  
Address 2: \_\_\_\_\_  
City: Oklahoma City State: OK Zip: 73112 + 1483  
Contact Person: Candy Driscoll  
Phone: (405) 246-3140  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Basal Chester Depth to Top: 5678' Bottom: 5700' T.D. 5850'  
Sqz - KS City Depth to Top: 4698' Bottom: 4712' T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 025-21279-00-0  
Spot Description: \_\_\_\_\_  
C - NW NE Sec. 11 Twp. 34 S. R. 24  East  West  
660 Feet from  North /  South Line of Section  
1,980 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Clark  
Lease Name: Gardiner 11 Well #: 1  
Date Well Completed: 4/14/2005  
The plugging proposal was approved on: 3/31/2010 (Date)  
by: Eric Macleron (KCC District Agent's Name)  
Plugging Commenced: 3/31/2010  
Plugging Completed: 4/02/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
5678-5700'	Oil & Water	Surface	8 5/8"	809'	None
4698-4712'	Oil & Water	Production	4 1/2"	5850'	3043'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pull out w/ rods & tbg . Load csg w/ mud & set 4 1/2" 10K CIBP @ 4648' , cap w/ 2 sks cement . Cut & pull 4 1/2" csg from 3043' ( 67 jts ) . Run tbg @ 1059' , mix & spot 120 sks Class "C" cement up to 620' , pull up hole w/ tbg @ 300' & spot 40 sks cement up to 150' , POH w/ tbg & top out 54' - 4' w/ 15 sks cement. Dig out & cut off wellhead 4' below ground level & weld ID plate .

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc.  
Address 1: P. O. Box 1706 Address 2: \_\_\_\_\_  
City: Duncan State: OK Zip: 73534 + 1706  
Phone: (580) 467-0258  
Name of Party Responsible for Plugging Fees: EOG Resources, Inc.  
State of Oklahoma County, Oklahoma, ss.  
Candy Driscoll  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Candy Driscoll

RECEIVED  
APR 07 2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA