

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34318  
Name: Berexco, L.L.C.  
Address 1: P. O. Box 723  
Address 2: P. O. Box 20380, Wichita, KS 67206  
City: Hays State: KS Zip: 67601 +  
Contact Person: Robert Grant  
Phone: ( 785 ) 628-6101  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Sampson Depth to Top: 3342 Bottom: 3358 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 159-19153-00-01  
Spot Description: \_\_\_\_\_  
SE SW NW Sec. 2 Twp. 21 S. R. 9  East  West  
290 3026 Feet from  North  South Line of Section  
990 4428 Feet from  East  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Rice  
Lease Name: Gillen OWVO Well #: 3  
Date Well Completed: 1-24-64  
The plugging proposal was approved on: 4-13-10 (Date)  
by: Virgil Clothier (KCC District Agent's Name)  
Plugging Commenced: 4-13-10  
Plugging Completed: 4-13-10

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |         | Casing Record (Surface, Conductor & Production) |       |               |            |
|---------------------------|---------|---|-------|---------------|------------|
| Formation                 | Content | Casing  | Size  | Setting Depth | Pulled Out |
|                           |         |   | 8 5/8 | 200'          | 0          |
|                           |         |   | 5 1/2 | 3454'         | 0          |
|                           |         |   |       |               |            |
|                           |         |   |       |               |            |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Lockset @ 2900' put 2 sx cement on top. Perf 2 holes 1200', 750' and 250'. Run tubing to 1204' spot 35 sx 60/40 pos 4% gel. Pull to 749' spot 35 sx 60/40 pos 4% gel. Pull to 262' mix 50 sx 60/40 pos 4% gel, circ out 5 1/2, shut 5 1/2 in, mix 65 sx 60/40 pos 4% gel, circ out 8 5/8. Pull tubing, hook to 5 1/2, mix 24 sx 60/40 pos 4% gel, circ out 8 5/8 shut in 50#.

RECEIVED

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.  
Address 1: P. O. Box 723 Address 2: P. O. Box 20380, Wichita, KS 67206  
City: Hays State: KS Zip: 67601 +  
Phone: ( 785 ) 628-6101  
Name of Party Responsible for Plugging Fees: Robert Grant  
State of Kansas County, Sedgwick ss.  
Robert Grant  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Robert Grant