

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 9408  
Name: Trans Pacific Oil Corporation  
Address 1: 100 S Main Ste 200  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67202 + 3735  
Contact Person: Glenna Lowe  
Phone: (316) 262-3596  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 167-20222-00-00  
Spot Description: \_\_\_\_\_  
NE NE SE Sec. 24 Twp. 14 S. R. 11  East  West  
2,310 Feet from  North /  South Line of Section  
330 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Russell  
Lease Name: Stoppel Well #: 1  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Case Morris (KCC District Agent's Name)  
Plugging Commenced: 5/4/11  
Plugging Completed: 5/11/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	307	225 Sacks Cement
		Production	5.5	2908	75 Sacks Cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing & drilled with tongs, washed down to 350'. Ran tubing to 350'. Milled on steel, couldn't get back in casing. Pulled tubing & ran back in with bit. Drilled to 465. Ran tubing to 465' & drilled to 500'. perforated at 470' & pumped 80 sacks cement to surface. Pulled tubing & topped with 5 sacks cement. Hooked up to 5 1/2" casing & pumped 5 sacks cement. Cut off 8 5/8" & 5 1/2" casing 4' below ground. Topped with 30 bags cement.

RECEIVED  
MAY 27 2011

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc  
Address 1: 190 US Hwy 56 Address 2: \_\_\_\_\_  
City: Ellinwood State: KS Zip: 67526 + \_\_\_\_\_  
Phone: (620) 727-3410

KCC WICHITA

Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation

State of Kansas County, Sedgewick, ss.  
Glenna Lowe (Print Name)  Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Glenna Lowe