

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Tri United, Inc
Address: 950 270th Ave Hays, Ks 67601
Phone: (785) 628-3670 Operator License #: 03194
Type of Well: oil well Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4-8-11 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3294' Bottom: 3520' T.D. _____
Arb Depth to Top: 3597' Bottom: 3603' T.D. 3603'
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-00853-00-00
Lease Name: Brull (Formerly Leiker A)
Well Number: #1
Spot Location (QQQQ): SW - SE - NW - _____
2470 Feet from North / South Section Line
2310
3630
1650 Feet from East / West Section Line
Sec. 2 Twp. 15 s. R. 18 East West
County: Ellis
Date Well Completed: 8-20-56
Plugging Commenced: 4-13-11 2:00 pm
Plugging Completed: 4-13-11 4:30 pm

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
KC	Limestone	3294'	3520'	5 1/2	3598'	none
surface	sand & clay	0	200'	8 5/8	208'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
perforated 5 1/2 at 1650' & 1200" & 550" & 200' Ran tubing to 2650' spot 50 sks cement, pull tubing to 1600' spot 165sks cement & 500# hulls, pull to 850' pumped 120sks cement & 500# hulls Circulated to surface. Pulled out Tubing. Tied on 5 1/2 pumped 30sks cement, circulated thru 8 5/8. Shut in with 400# pressure.

Name of Plugging Contractor: Tri United, Inc License #: 03194
Address: 950 270th Ave Allied Cementing co Hays, Ks 67601
Name of Party Responsible for Plugging Fees: Tri United, Inc
State of KS County, Ellis, ss.

Eugene Leiker (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Eugene E. Leiker
(Address) 950 270th Ave Hays. Ks 6701
SUBSCRIBED and SWORN TO before me this 8 day of June, 20 11
My Commission Expires: 4-9-13
Notary Public