

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6127
Name: Jeff Koron dba Taurus Oil Company
Address 1: PO Box 981
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Jeff Koron
Phone: (785) 628-1727
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3860 Bottom: 3870 T.D. 3870'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-051-21583-00-00
Spot Description: _____
SW SW SW Sec. 22 Twp. 13 S. R. 20 East West
330 Feet from North / South Line of Section
4,950 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Herman Well #: 4
Date Well Completed: 1/10/1979
The plugging proposal was approved on: 4/16/2011 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 5/31/2011
Plugging Completed: 5/31/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	210'	None
Arbuckle	Oil & Water	Production	5 1/2"	3862'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Spot 75 sxs cmt, then 15 sxs gel w/200# hulls.
Followed this with 270 sxs cmt w/200# hulls at 300 psi max, 300 psi shut in.
8 5/8" X 5 1/2" anullus was full of cmt, visual in braden head.
Total of 345 sxs 60/40 Poz Mix, 4% gel & 300# hulls.

RECEIVED
JUN 09 2011
KCC WICHITA

Plugging Contractor License #: 99996 Name: Allied Cementing Company, LLC
Address 1: PO Box 31 Address 2: _____
City: Russell State: KS Zip: 67665 + _____
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: Jeff Koron dba Taurus Oil Company
State of Kansas County, Ellis, ss.
Roger L. Moses Employee of Operator or Operator on above-described well.
(Print Name)
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Roger L. Moses

Mall to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DR

