

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 310000  
Name: Prater Oil & Gas Operations  
Address 1: 1303 N. Main  
Address 2: \_\_\_\_\_  
City: Pratt State: KS Zip: 67124 + \_\_\_\_\_  
Contact Person: Ron Prater  
Phone: (620) 770-2232  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 4610 Bottom: 4611 T.D. 4784  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 151-21455 00.00  
Spot Description: \_\_\_\_\_  
SW SW SW \_\_\_\_\_ Sec. 14 Twp. 29 S. R. 13  East  West  
330 337 Feet from  North /  South Line of Section  
4950 5006 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Pratt  
Lease Name: Mason Well #: A-3  
Date Well Completed: 8/1/1994  
The plugging proposal was approved on: 5/26/2011 (Date)  
by: Jerry Stapleton (KCC District Agent's Name)  
Plugging Commenced: 5/27/2011  
Plugging Completed: 5/31/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	817	None
		Production	4 1/2	4785	2200

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 4560', spot 2sx cement on bridge plug with dump bailer, lay down casing, run tubing to 840', 1st, pump 12sx gel, 200 hulls, 50sx 60/40 POZ 4% gel cement, 2nd 350', 40sx 60/40 POZ, 3rd 60', circulate 20sx cement to surface

RECEIVED  
JUN 10 2011

Plugging Contractor License #: 5105 Name: Clarke Corporation  
Address 1: P.O. Box 187 Address 2: 107 W. Fowler  
City: Medicine Lodge State: KS Zip: 67104 + \_\_\_\_\_  
Phone: (620) 886-5665  
Name of Party Responsible for Plugging Fees: Prater Oil & Gas Operations  
State of Kansas County, Barber, ss.

KCC WICHITA

Mark Morgenstern  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Mark Morgenstern

DK