

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3911
Name: Rama Operating Co, Inc
Address 1: 101 S. Main St.
Address 2: _____
City: Stafford State: KS Zip: 67578 + 1429
Contact Person: Robin L. Austin
Phone: (620) 234 5191
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 175-00208-00 00
Spot Description: _____
N 2 1/2 SE SE Sec. 23 Twp. 33 S. R. 31 East West
560 Feet from North / South Line of Section
660 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Seward
Lease Name: Wheatley A Well #: 3
Date Well Completed: _____
The plugging proposal was approved on: 4-6-10 (Date)
by: Eric MacLaren (KCC District Agent's Name)
Plugging Commenced: 4-12-10
Plugging Completed: 4-14-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			10 3/4	2406	—
			7	5998	2515

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped mud down 7. LogTech set CIBP @ 4840. Set 2nd CIBP + 3 sx cmt. from 2670 to 2655. Shot + pull 7. to 2430. Circ. hole w/mud + mixed 60 sx plug from 2430 to 2300. 30 sx 1600 to 1535 35 sx 600 to 525 15 sx 40 to 0 Capped 10 3/4 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc.
Address 1: Rt 1 Box 49 BA Address 2: _____
City: Tyrone State: OK Zip: 73951 + 9731
Phone: (580) 854 6515
Name of Party Responsible for Plugging Fees: RAMA Operating Co.
State of KANSAS County: STAFFORD, ss.
Robin L. Austin Employee of Operator or Operator on above-described well
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature]

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

MAY 04 2010
5-4-10
KCC WICHITA