

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 30269  
Name: Argent Energy, Inc.  
Address 1: 1313 N. Webb Rd., Suite 210  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67206 + 4077  
Contact Person: James C. Remsberg  
Phone: ( 316 ) 262-5111  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Marmaton Depth to Top: 4220' Bottom: 4224' T.D. \_\_\_\_\_  
Ft. Scott Depth to Top: 4376' Bottom: 4380' T.D. 4435'  
Mississippian Depth to Top: 4450' Bottom: 4479' T.D. \_\_\_\_\_

API No. 15 - 135-22,848 00 00  
Spot Description: \_\_\_\_\_  
NE NW SW \_\_\_\_\_ Sec. 16 Twp. 18 S. R. 25  East  West  
2,310 Feet from  North /  South Line of Section  
800 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ness  
Lease Name: Ryan Well #: 3  
Date Well Completed: 8/24/85  
The plugging proposal was approved on: 11/19/09 (Date)  
by: Steve Bond (KCC District Agent's Name)  
Plugging Commenced: 3/30/10  
Plugging Completed: 3/30/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
L-KC 3858-4179	water	Surface	8 5/8	261'	none
Marm. 4218-4290	dry	Production	4 1/2	4471'	none
Ft. Scott 4358-4383	Water				
Miss. 4450'-4479'	water				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Spot 25 sx w/ 100# cottonseed hulls @ 4360'. Pull tbg to 1800'; pump 115 sx @ 1800' - circulated to surface. Pump 20 sx down annulus. Dump 30 sx to top of casing. Plugging witnessed by Michael Maier for the KCC.

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 05 2010

Plugging Contractor License #: 32382 Name: Swift Services, Inc. CONSERVATION DIVISION  
WICHITA, KS

Address 1: P.O. Box 466 Address 2: \_\_\_\_\_

City: Ness City State: KS Zip: 67560 + 0466

Phone: ( 785 ) 798-2300

Name of Party Responsible for Plugging Fees: Argent Energy, Inc.

State of Kansas County, Sedgwick, ss.

James C. Remsberg  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God

Signature: James C. Remsberg

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202