

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: COLT ENERGY, INC
Address: P O BOX 388, IOLA, KS 66749
Phone: (620) 365-3111 Operator License #: 5150
Type of Well: SWD Docket #: D-26,142.0
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4/13/10 (Date)
by: JOHN ALMOND (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
MISSISSIPPI LIME Depth to Top: 1209 Bottom: 1410 T.D. 1410

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-001-27,300 0001
Lease Name: KEOWN
Well Number: 2W(WDW)
Spot Location (QQQQ): _____ - NW - SW - SW
705 Feet from North / South Section Line
4890 Feet from East / West Section Line
Sec. 22 Twp. 23 S. R. 18 East West
County: ALLEN
Date Well Completed: 6/28/85
Plugging Commenced: 3/18/10
Plugging Completed: 4/13/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
SURFACE				8 5/8	20'	NONE
PRODUCTION CSG		1209	1410	5 1/2	1209	NONE


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

3/18/10 COMPANY UNIT RAN 1375' 1" TUBING 4/13/10 CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION THRU 1" TUBING TO TD-- MIXED & PUMPED 50SXS 50/50 POZ MIX W/6% PULLED 1" TO 950' MIX & PUMP 50SXS CEMENT PULLED 1" TO 500' PUMPED 40SXS TO SURFACE PULL 1" TOPPED WELL OFF W/3SXS TOTAL CEMENT USED 143SXS. WELL PLUGGED

Name of Plugging Contractor: CONSOLIDATED OIL WELL SERVICES License #: 31440 RECEIVED KANSAS CORPORATION COMMISSION
Address: P O BOX 884 CHANUTE, KS 66720 MAY 05 2010

Name of Party Responsible for Plugging Fees: COLT ENERGY, INC CONSERVATION DIVISION WICHITA, KS
State of KANSAS County, ALLEN, ss.

DENNIS KERSHNER (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Dennis Kershner

(Address) P O BOX 388, IOLA, KS 66749

SUBSCRIBED and SWORN TO before me this 30th day of April, 2010

Shirley A Stotler My Commission Expires: 1-20-2012
Notary Public

COLT ENERGY, INC. — OIL OPERATION ^{274 hrs}

WELL PULLING RECORD

Date 3-18-10

Lease Name Keown Well No. 2W-404W

Reason for Pulling _____

Type of Pump Removed _____

Special Equip. Removed (Anchors, Checks, etc.) _____

T.D., SLM _____ Fluid Level from Surface _____

Well Conditions Seen (Corrosion, Gas, Gyp, Paraffin, Sand, etc.) _____

Chemical Treatment (Kind and Amount) _____

Type of Pump Run In _____

Special Equipment (Anchors, Checks, etc.) Run In _____

1375'

Additional Information; including jack or other repairs, tubing clamp loose, and oil cleanup.

Run 55 joints of 1" in well to plug

Called In By _____ Signed By Butch

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 05 2010

CONSERVATION DIVISION
WICHITA, KS



CONSOLIDATED
Oil Well Services, LLC

TICKET NUMBER 22589
LOCATION Ottawa KS
FOREMAN Fred Maden

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT

CEMENT 5w/4

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
4/13/10	1828	Keown # 2.w(wdw)	22 22	23S	18E	AL
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
Colt Energy Inc			506	Fred	Safety Mtg	
MAILING ADDRESS			495	Casey	CK	
112 Rhode Island			503	Derek	DM	
CITY	STATE	ZIP CODE				
Iola	KS	66749				

JOB TYPE Plug HOLE SIZE - HOLE DEPTH 1410 CASING SIZE & WEIGHT 5 1/2
 CASING DEPTH 8 DRILL PIPE 1" TUBING 1400' OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT In CASING Full
 DISPLACEMENT N/A DISPLACEMENT PSI _____ MIX PSI _____ RATE 1 1/2 BPM

REMARKS: Establish circulation thru 1" Tubing. Mix + Pump 50 SKS
Cement. Pull 1" to 950' Mix + Pump 50 SKS Cement Pull 1"
to 500' Cement to Surface. Pull remaining 1" + Top off
Well. 143 SKS 80/50 For Mix Cement 6% Gel Total.

Customer Supplied Chewy Water.

Fred Maden

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405N	1	PUMP CHARGE <u>Plug to Abandon</u>		900 ⁰⁰
5406	-0-	MILEAGE <u>Truck on lease</u>		N/C
5407A	270.27	<u>Top Miles</u>		324.33
1124	135 SKS	50/50 Poz Mix Cement		1289 ²⁵
118B	721#	Premium Gel		122 ⁵⁷
		<u>WO # 233769</u>		
			RECEIVED KANSAS CORPORATION COMMISSION	
			MAY 05 2010	
			CONSERVATION DIVISION WICHITA, KS	
			6.3% SALES TAX	88 ⁹⁴
			ESTIMATED TOTAL	2725 ⁰⁸

Ravin 3737

AUTHORIZATION

Melvin L. Norman

TITLE

DATE