

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 3288  
Name: Jody Oil & Gas Corporation  
Address 1: PO Box 422  
Address 2: \_\_\_\_\_  
City: Attica State: KS Zip: 67009 + \_\_\_\_\_  
Contact Person: Randy Newberry  
Phone: ( 620 ) 254-7251  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: E26065.1  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 007-21870-00-01  
Spot Description: C NE NE NE  
C NE NE NE Sec. 36 Twp. 32 S. R. 11  East  West  
4953 4938 Feet from  North /  South Line of Section  
454 320 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barber  
Lease Name: Coleman Well #: 2  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: 4/8/2010 (Date)  
by: Steve Durant (KCC District Agent's Name)  
Plugging Commenced: 4/12/2010  
Plugging Completed: 4/14/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	262	185 sacks cement
		Production	4.5	4616	225 sacks cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand @ 4420'. Bailed 4 sacks cement. Cut surface off 4' below ground. Had 16 inches stretch. Ripped casing @ 2640', 2410', 2230' & 2040'. Came loose @ 2040'. Pulled casing up to 900'. Pumped 15 gel, 50 sacks 3% cc & 50# hulls. Pulled to 600' & pumped 50 sacks & 50 # hulls. Pulled to 270' & pumped 40 sacks & 50# hulls. Pulled to 40' & pumped 20 sacks to surface.

RECEIVED  
MAY 17 2010

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.  
Address 1: 190 US HWY 56 Address 2: \_\_\_\_\_  
City: Ellinwood State: KS Zip: 67526 + 8911  
Phone: ( 620 ) 727-3409  
Name of Party Responsible for Plugging Fees: Jody Oil & Gas Corporation  
State of Kansas County, Harper, ss.  
Jody Oil & Gas Corporation  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


Signature: Randy Newberry

# QUALITY OILWELL CEMENTING, INC.

Phone 785-483-2025  
Cell 785-324-1041

Home Office P.O. Box 32 Russell, KS 67665

No. 3673

Date	4-14-10	Sec.	36	Twp.	32	Range	11	County	Barber	State	Ks	On Location		Finish	5:00								
Lease	Coleman			Well No.	2		Location Sharon																
Contractor	Quality Well Service						Owner To Quality Oilwell Cementing, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.																
Type Job	PTA						Charge To Jody oil + Gas																
Hole Size							T.D.																
Csg.	4 1/2						Depth																
Tbg. Size							Depth																
Tool							Depth																
Cement Left in Csg.							Shoe Joint																
Meas Line							Displace																
<b>EQUIPMENT</b>												<b>CEMENT</b>											
Pumptrk	6	No.		Cementer	Dave		Amount Ordered									160	5x	60	40	4%			
				Helper			Common									96							
Bulktrk	3	No.		Driver	Rich		Poz. Mix									64							
				Driver	John		Gel.									20							
Bulktrk		No.		Driver			Calcium									15x							
<b>JOB SERVICES &amp; REMARKS</b>																							
Remarks:												Hulls				150 #							
1 <sup>st</sup> pumped 1590' 50sx 3%CC 80.50# hulls @ 900'												Salt											
												Flowseal				15 gel on side							
2 <sup>nd</sup> pumped 50sx 50# hulls @ 600'																							
3 <sup>rd</sup> pumped 40sx 50# hulls @ 270'												Handling				181							
												Mileage				40							
4 <sup>th</sup> pumped 20sx @ 40' to surface																							
												RECEIVED				FLOAT EQUIPMENT				MAY 17 2010			
																KCC WICHITA							
												Guide Shoe											
												Centralizer											
Baskets																							
AFU Inserts								4 1/2 plug															
Pumptrk Charge																							
Mileage								40															
								Tax															
								Discount															
								Total Charge															
X Signature <u>Daniel B</u>																							