

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-063-21,305-00-00

LEASE NAME Albin

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1

4290 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 30 TWP. 14S RGE. 27 (E/W) (W)

COUNTY Gove

LEASE OPERATOR Energy Exploration, Inc.

ADDRESS 1002 S. Broadway, Wichita, KS 67211

PHONE# (316) -267-7336 OPERATORS LICENSE NO. 5063

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 1/11/90

Plugging Commenced 1/11/90

Plugging Completed 1/11/90

The plugging proposal was approved on 1-11-90 (date)

by Dale Balthazor (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	208.26'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4400'-1980' 10 sks cement @ 40'
25 sks cement @ 1980' 10 sks cement mousehole
100 sks cement @ 960' 15 sks cement rathole
40 sks cement @ 240'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Energy Exploration, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kyle B. Branum

(Address) P.O. Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 12th day of January, 1990

Glenda R. Tiffin, Notary Public

My Commission Expires: 2-6-92

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Energy Exploration, Inc.
1002 S. Broadway
Wichita, Kansas 67211

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Albin

WELL #1

LOCATION: C S/2 N/2 NW/4
Section 30-14S-27W
Gove County, Kansas

LOGGERS TOTAL DEPTH: 4400'

ROTARY TOTAL DEPTH: 4400'

COMMENCED: 1/3/90

CASING: 8-5/8" @ 208.26' w/140 lbs cement

ELEVATION: 2510' K.B.

COMPLETED: 1/11/90

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	210'	Shale	2465'
Dakota Sand	930'	Kansas City	3751'
Red Bed	980'	Pawnee	4109'
Cedar Hills	1538'	Ft. Scott	4209'
Shale	1720'	Mississippi	4320'
Anhydrite	1952'	R.T.D.	4400'
Red Bed	1987'		

ST...
JAN 15 1990
COUNTY OF RUSSELL

STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)

Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Kyle B. Branum

Kyle B. Branum

Subscribed and sworn to before me on January 12, 1990.

My commission expires: February 6, 1992.

GLEND A. R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-92

Glenda R. Tiffin

Glenda R. Tiffin, Notary Public