

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-063-21,060-00-00
 LEASE NAME Albin "A"

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1
4950 Ft. from S Section Line
4950 Ft. from E Section Line
 SEC. 30 TWP. 14S RGE. 27 (E) or (W)
 COUNTY Gove

LEASE OPERATOR K & E Petroleum, Inc.
 ADDRESS 100 S. Main, Suite 300, Hardage Ctr., Wichita, KS
 PHONE#(316) 264-4301 OPERATORS LICENSE NO. 5267

Date Well Completed 9-24-86
 Plugging Commenced 9-24-86
 Plugging Completed 9-24-86

Character of Well D & A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes
 Which KCC Office did you notify? District #6, Marion Schmidt, state plugger.
 Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	256'	None


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped heavy mud to 1980'; 1st plug from 1980' to 1860' w/30 sx; pumped heavy mud to 990';
2nd plug from 990' to 590' w/100 sx + 1 sx. Celoflake; 3rd plug from 300' to 140' w/40 sx;
4th plug from solid bridge at 40' to surface w/10 sx; 15 sx. in rathole. All cement 50/50
posmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422
 Address 801 Union Center, Wichita, KS 67202
 STATE OF Kansas COUNTY OF Sedgwick, ss.

Abercrombie Drilling, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters contained and the log of the above-described well as filed that the same are true and correct, and I help me God.

(Signature) [Signature]
 (Address) 801 Union Center, Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 26th day of September, 19 86
Judy L. Heitkotter
 Notary Public
 My Commission Expires: 6-24-89

09-30-86