

15-167-30235-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Russell County, Sec. 7 Twp. 14S Rge. 12W (EX) (W)  
Location as "NE/CNW/SW" or footage from lines NE NW SW  
Lease Owner Martin & Keller  
Lease Name Boldridge Well No. 1  
Office Address 1035 Kennedy Bldg., Tulsa, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-13-66 19    
Application for plugging filed 7-13-66 19    
Application for plugging approved 7-13-66 19    
Plugging commenced 7-13-66 19    
Plugging completed 7-13-66 19    
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production                      19    
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Russell, Kansas  
Producing formation                      Depth to top                      Bottom                      Total Depth of Well 3339 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	214'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from                      feet to                      feet for each plug set.

1st Plug set @ 210' w/ 1/2 sk. hulls & 25 sks. cem.  
2nd Plug set @ 40' w/ 1/2 sk. hulls & 10 sks. cem.

*Handwritten notes and stamps:*  
JUL 20 1966  
07-20-1966  
Conservation Division  
State Corporation Commission  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
P. O. Box 486, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of July, 1966

Gloria Nichols  
Notary Public.

My commission expires April 1, 1967

15-167-30235-00-00

DRILLER'S LOG

COMPANY:	Martin & Keller
CONTRACTOR:	LEBEN DRILLING, INC.
FARM:	BOLDRIDGE #1
LOCATION:	NE NW SW SEC. 7-14S-12W RUSSELL COUNTY, KANSAS
COMMENCED:	7-5-66
COMPLETED:	7-13-66

-----

0	45	Post Rock, Clay
45	365	Shale
365	380	Shale with Streaks Hard Sand
380	440	Sand, Shale
440	754	Redbed
754	790	Anhydrite
790	1400	Shale, Shells
1400	1650	Shale with Lime Streaks
1650	1760	Lime with Shale Streaks
1760	1935	Lime, Shale
1935	2357	Shale, Lime
2357	2430	Shale with Lime, Sand
2430	2620	Shale, Lime
2620	2690	Lime, Shale
2690	2915	Lime
2915	2960	Shale, Lime
2960	3312	Lime
3312	3318	Conglomerate
3318	3339	Arbuckle
	<u>3339</u>	<u>RTD - D. &amp; A.</u>

RECORDED  
 JUL 20 1966  
 07-20-1966  
 CONSERVATION DIVISION  
 STATE OF KANSAS

-----

Set 8 5/8" used surface casing @ 214' cemented with 150 sacks  
Common, 2% cc

-----

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Boldridge #1 well, located NE NW SW of Section 7, Township 14 South, Range 12 West, Russell County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 18th day of July, 1966.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:  
April 1, 1967