

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-22,630-00-00

LEASE NAME Blue

WELL NUMBER 1

SPOT LOCATION SW NW NW

SEC. 2 TWP. 14 RGE. 2 (E) or (W)

COUNTY Russell

Date Well Completed 7-23-85

Plugging Commenced 7-23-85

Plugging Completed 7-23-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Box 709, Russell, Kansas 67665

PHONE (313) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well D & A
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	727'	Cmtd. w/325 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from _____ feet to _____ feet each set. Spot 25 sax cement @3,305' thru 4 1/2" drill pipe. Push bridge plug to 740', spot 25 sax cement on plug thru 4 1/2" drill pipe. Push bridge plug to 570', spot 80 sax cement on plug thru 4 1/2" drill pipe. Push bridge plug to 240' spot 40 sax cement on plug thru 4 1/2" drill pipe. Push bridge plug to 40' w/1 sax hulls on plug, dump 10 sax cement on plug to cellar. Dump 10 sax cement down rat hole, dump 6 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co., Inc. License No. 164
Address Box 709, Russell, Kansas 67665

STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF RUSSELL, ss. AUG 21 1985
0821-1985

Jack P. Beeman, Sec.-Treas.(employee of operator) or _____
(~~XXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Box 709, Russell, Kansas 67665

SUBSCRIBED AND SWORN TO before me this 20th day of August, 1985

Ruth Phillips
Notary Public

My Commission expires: 