

15-1167-00394-00-00

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Russell County. Sec. 8 Twp. 14 Rge. (E)12 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SE SE SE
Lease Owner. Royer-Farris Drilling Co.
Lease Name. Mahoney Well No. 1
Office Address. 709 Brown Bldg., Wichita 2, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole). Oil
Date well completed. 12-7 1945
Application for plugging filed. 7-24 1946
Application for plugging approved. 8 1946
Plugging commenced. 8-18 1946
Plugging completed. 8-19 1946
Reason for abandonment of well or producing formation. Pumped out.

NORTH

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. Kerr
Producing formation. Depth to top. Bottom. Total Depth of Well. Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Mudded hole with heavy mud to 250 ft. bridged and cemented with 15 sax cement mud to 30 ft. bridged and cemented with 10 sax cement to base of cellar.

07-31-1947

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to. Royer-Farris Drilling Co.
Address. 709 Brown Bldg., Wichita, 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. A. Farris (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

709 Brown Bldg., Wichita 2, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of July, 1947.
Effie J. Foote
Notary Public.

My commission expires April 23, 1949.

PLUGGING
FILE SEC 8 T 14 R 2W
DATE 63 PAGE 35

15-167-00394-00-00

MANDREY #1, SW SW SW Section 5, Township 14, South, Range 12, West, Russell County, Kansas.

Contractors: Meyer-Farris Drilling Co.
Drilling Started: November 29, 1945.
Drilling Completed: December 7, 1945.
Elevation: 1806'
 362.70' of 2 3/8" surface pipe cemented with 125 sacks cement.

| | | |
|------|------|------------------------|
| 0 | 43 | shale and shells |
| 43 | 275 | shale lime and sand |
| 275 | 300 | lime sand |
| 300 | 360 | shale and shells |
| 360 | 480 | shale shells and sand |
| 480 | 670 | red rock |
| 670 | 720 | red shale |
| 720 | 765 | amphibrite lime |
| 765 | 860 | lime |
| 860 | 945 | red bed and shale |
| 945 | 1020 | shale and shells |
| 1020 | 1135 | shale |
| 1135 | 1185 | salt |
| 1185 | 1360 | shale |
| 1360 | 1797 | lime and shale |
| 1797 | 1895 | lime |
| 1895 | 2300 | lime and shale |
| 2300 | 2405 | shale and shells |
| 2405 | 2645 | shale and lime |
| 2645 | 2770 | lime |
| 2770 | 2920 | lime and shale |
| 2920 | 3089 | lime |
| 3089 | 3145 | lime and shale streaks |
| 3145 | 3195 | lime |
| 3195 | 3302 | shale and lime |
| 3302 | 3330 | lime |

Berrick Floor Measurements.

| | |
|---------------------|---|
| Hooker Shale | 2862 |
| Hedge Line | 2890 G. O. 2892-96 |
| Leaning | 2935 Good show oil and odor 2970-93 |
| Cherty Conglomerate | 3270 |
| Artuskie | 3300 no shows |
| Total Depth | 3330 |
| 3 1/2' | 3100 cemented with 125 sacks cement |
| Shot 45 shots | 2968-76 |
| 9000 gal. acid | |
| Preliminary test | Stubbed and flowed 23 bbls. oil per hour. No water. |

K. K. Meyer does hereby swear that he is a partner of the firm, Meyer-Farris Drilling Company, who were the drilling contractors on the above described well and that the above log is true and correct to the best of his knowledge and belief.

8 14 1210 H. K. Meyer
 63 35

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BE IT REMEMBERED, That on this 19th day of December, A. D. 1945, before me, a notary public in and for said County and State, personally appeared K. K. Meyer to me known to be the identical person described in and who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my official signature and affixed my notarial seal, the day and year first above written.

E. J. Fouts
 Notary Public

My Commission expires April 23, 1949.