

15-167-21990-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Russell SEC. 8 TWP. 14 RGE. 12W E/W  
 Location as in quarters or footage from lines:  
560' FSL-330' FEL SE SE


Lease Owner Mineral Management Corp.  
 Lease Name Mahoney Well No. 1  
 Office Address 530 Brdwy. Plaza, Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced November 12, 1983  
 Plugging completed November 17, 1983  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
 correctly on above  
 Section Platt.

Depleted  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	741	None
				4-1/2"	3049'	2456.25'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dump 4 sacks cement on bottom. Sanded to 2930' and dumped 4 sacks cement. Pulled 61 joints of 4 1/2" casing. Squeezed well with 4 sacks hulls, 20 sacks gel, 1 sack hulls, released plug and pumped 165 sacks 50/50 Pozmix cement with 6% added gel and 3% calcium chloride. Maximum pressure was 700 PSI and shutin at 400 PSI

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.


STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold

James W. Rockhold, Box 698, Great Bend, Ks.  
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 18th day of November, 1983



Iona M. Leatherman  
 Notary Public.

My Commission expires:

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 21 1983  
 11-21-1983  
 CONSERVATION DIVISION  
 Wichita, Kansas