

API NUMBER 15-167-22,637-00-00

LEASE NAME Mahoney

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #2

990 Ft. from S Section Line

4290 Ft. from E Section Line

LEASE OPERATOR Jerry J. Driscoll Oil Investment, Inc.

SEC. 8 TWP. 14 RGE. 12 (E) or (W)

ADDRESS P. O. Box 921, Russell KS 67665

COUNTY Russell

PHONE# (913) 483-2416 OPERATORS LICENSE NO. 7482

Date Well Completed 7/26/85

Character of Well D&A

Plugging Commenced 7/26/85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/26/85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? 6

Is ACO-1 filed? No If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		-0-	329'	8-5/8"	329'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 3025' - 760'

20 sks cement @ 760' 10 sks cement in rat hole

80 sks cement @ 400'

10 sks cement @ 40'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665


STATE OF Kansas COUNTY OF Russell, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____

(Address) P. O. Box 506, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 30th day of July, 19 85



RECEIVED Glenda R. Tiffin Notary Public
 STATE OF KANSAS
 My Commission Expires February 6, 1988

07-31-1985
 JUL 31 1985

AUG 8 1985

15-167-~~30050~~-00-00
-22637-

EMPHASIS OIL OPERATIONS

P. O. Box 506
Russell, KS 67665

DRILLERS LOG

OPERATOR: Jerry J. Driscoll Oil
Investment, Inc.
Box 921
Russell, KS 67665

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Mahoney WELL #2

LOCATION: NE SW SW
Section 8-14S-12W
Russell County, Kansas

Rotary Total Depth: 3025'

Elevation: 1830' K.B.

Commenced: 7/22/85

Completed: 7/26/85

Casing: 8-5/8" @ 329' w/170 sks cement

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)


Top soil & Post rock	40'	Redbed & Shale	754'
Post rock	75'	Anhydrite	786'
Sand & Clay	150'	Shale	2186'
Dakota	230'	Lime & Shale (R.T.D.)	3025'

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1985
08-08-1985
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
 ss
COUNTY OF RUSSELL)

Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum


RECEIVED
STATE CORPORATION COMMISSION

Subscribed and sworn to before me this 30th of July, 1985.

My Commission Expires: February 6, 1988.

7111-31 1985




Glenda R. Tiffin, Notary Public