

15-169-00227-00-00

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 18 1962  
05-18-1962  
CONSERVATION DIVISION  
WICHITA, KANSAS

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Saline

Location; C W/2 S1 NW Sec. 10 Twp. 14 Rge. 2 (EX) (W)

Name of Field: Wild Cat Total Depth: 3175

I have this date completed supervision of plugging of:

Lease Name: Mattison Well No. I

Operator's Full Name: Don McKallar

Complete Address: 1321 Pershing Salina, Kansas

Plugging Contractor Blackstone Drilling Co.

Address: Peoples State Bk. Bldg. McPherson, Kansas License No. Rotary

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated; \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No X

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour \_\_\_\_\_ IO:AM \_\_\_\_\_ Day 6 Month 5 Year 62

The above well was plugged as follows:

Filled hole w/ 36 vis mud from T.D. 3175' back to 151' set a halco plug 1/4 sack hulls and 25 sack cement from 140' back to 65'. Filled hole w/ 36 vis mud from 65' back to 30' set a halco plug 1/4 sack hulls and ran 8 sack cement from 25' back to zero 3' below ground level. 8 5/8" surface pipe 3' below ground level. Filled rat hole w/ mud and 2 sack cement 3' below ground level.

Signed: Robert W. Jones  
Conservation Division Agent

Reviewed: Harold Hollis  
Field Supervisor

Remarks:

INVOICED  
DATE 5/21/62  
INV. NO. 5024-W