

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 22 1980

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -153-20, 633-00-00 (of this well)

Operator's Full Name Homer G. Krebbiel, Sr.

Complete Address 1343 N. Maple, McPherson, Kansas 67460

Lease Name Peterman Well No. 1

Location SW SW NW Sec. 30 Twp. 14 Rge. 8 (E) (W) X

County Ellsworth Total Depth 3400'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Co. and Sun Oil Well Cementing Co.

Address Box 1389, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 6:45 AM Day 12 Month September Year 1980

The above well was plugged as follows: 8 3/8" - 215' - 160 sacks - 2% gel - 3% cal. chlon

Hole Filled with mud. 40 sacks cement pumped through drill pipe at 500'. 25 sacks cement pumped through drill pipe at 210'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks. Rathole cemented with 5 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED  
DATE 9-24-80  
INV. NO. 3218-2