

15-063-30094-00-00

Form CP-3
6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

10-05-66
10-05-66
10-05-66

Operator's Full Name Pickrell Drilling Company,

Complete Address: 705 4th National Bank Building, Wichita, Kansas.

Lease Name Rohr Well No. B-2

Location CSE-NW Sec. 34 Twp. 14 Rge. (K) 27

County Gove Total Depth 3710

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Twisted off drill pipe, unable to fish well abandoned.

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 2:45PM Day 1 Month 10 Year 1966

The Above well was plugged as follows:

247'--8 5/8" Surface pipe, cement circulated with 165 Sx.

Twisted off drill pipe, left fish in hole.

Circulated hole from top of fish with heavy mud, set plug @ 500' and

displaced 25 Sx. cement thru DP. Heavy mud to 240', set plug and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

(Cementing by Globe Oil Well Cementing, Inc.)

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/5/66

INV. NO. 4056-U