

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Petroleum, Incorporated,

Complete Address: Garvey Building, Wichita, Kansas.

Lease Name Cheney Well No. 1

Location CNE-NE Sec. 33 Twp. 14 Rge. (E) (N) 27

County Gove Total Depth 4352

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drilling Company,

Address: Route #2, Great Bend, Kansas. License No. _____

Operation Completed: Hour 10:15 PM Day 5 Month 9 Year 1966

The Above well was plugged as follows:

217'--8 5/8" Surface pipe, cement circulated with 160 Sx.

Circulated hole with heavy mud, set plug @ 480' and displaced 20 Sx.

cement thru DP. Heavy mud to 200', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

SEP 9 1966

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 9/9/66

INV. NO. 3888-W