

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-205-25873-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 12-29S-15E  
420 feet from S Section Line, 1708 feet from E Section Line  
Lease Name: ROBERT Well #: 1  
County: WILSON Total Vertical Depth: 1183 feet

Operator License No.: 33074  
Op Name: DART CHEROKEE BASIN OPERATING  
Address: 600 DART RD PO BOX 177  
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	20		
T1	2.375	1130	1130	
PROD	4.5	1170		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/01/2011 12:00 PM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Revd. from: AARON HAMMERSCHMID Company: DART CHEROKEE BASIN Phone: (620) 331-7870

Proposed Plugging Method: TIH TO 1170'. SET CMT PLUG FR 1170' - SURF. CUT OFF CSG. RESTORE LOC.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 04/01/2011 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 1" cement string was lowered to 1150' and the well pumped full from btm to top thru this cement string. A total of 126 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
1090	1094		
1026	1028		
983	985		
968	970		
952	954		
893	896		
835	838		
820	822		
739	741		

RECEIVED

JUN 03 2011 AMD

KCC Chanute Dist. #3

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning  
(TECHNICIAN)

RECEIVED  
Form EP-2/3  
JUN 09 2011  
KCC WICHITA