

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-26766-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 30-29S-15E
750 feet from S Section Line, 2180 feet from E Section Line
Lease Name: SHIRE Well #: D3-30
County: WILSON Total Vertical Depth: 1314 feet

Operator License No.: 33074
Op Name: DART CHEROKEE BASIN OPERATING
Address: 600 DART RD PO BOX 177
MASON, MI 48854

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-------------|
| SURF | 8.625 | 44 | | 8 SX CMT. |
| T1 | 2.375 | 1267 | 1267 | |
| PROD | 4.5 | 1309 | | 135 SX CMT. |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/20/2010 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: AARON HAMMERSCHMID Company: DART CHEROKEE BASIN Phone: (620) 331-7870

Proposed
Plugging
Method:

TIH TO 1309'. SET CMT PLUG FR 1309' - SURF. CUT OFF CSG. RESTORE LOC.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: NONE
Date/Time Plugging Completed: 09/23/2010 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Tubing was run in the well to 1310'. The well was then pumped full of cement from btm to top thru this cement string. A total of 119 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1082 | 1084 | | |
| 950 | 952 | | |
| 876 | 879 | | |
| 776 | 777 | | |

RECEIVED
JUN 03 2011
KCC Chanute Dist. #3

AMD

Remarks:

Plugged through: TBG

District: 03

Signed Alan Dunning
(TECHNICIAN)

RECEIVED Form CP-2/3

JUN 09 2011

KCC WICHITA