

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-26118-00-01
Spot: SESWSENE Sec/Twnshp/Rge: 8-34S-11E
2763 feet from S Section Line, 941 feet from E Section Line
Lease Name: SPUR RANCH A Well #: 28
County: CHAUTAUQUA Total Vertical Depth: 1356 feet

Operator License No.: 5970
Op Name: ELMORE, JOHN A. OR PATRICIA R.
Address: 776 HWY 99
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40		10 SX
PROD	4.5	1410		160 SX

Well Type: EOR UIC Docket No: E20108.9 Date/Time to Plug: 05/04/2011 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: Phone: (620) 249-2519

Proposed Plugging Method: RUN 1" TUBIN TO 1400' GEL HOLE SPOT 10 SWKS CEMENT ON BOTTOM PULL 1" UP 10 1000' SPOT 10 SKSCEMENT PULL 1" UP TO 350' CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 05/05/2011 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1380' gelled hole and spotted 10 sack plug. Pulled up to 900' and spotted 5 sack plug. Pulled up to 380' and circulated cement to surface. Pulled 1" and topped well off. A total of 55 sacks of cement were used to plug this well.


RECEIVED
MAY 25 2011 DAS
KCC Chanute Dist. #3

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED
JUN 03 2011
KCC WICHITA
Form CP-2/3
to UIC
7/08