

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-00610-00-00
Spot: NESESW Sec/Twnshp/Rge: 2-18S-8W
1028 feet from S Section Line, 3032 feet from E Section Line
Lease Name: GOODWIN Well #: 1
County: RICE Total Vertical Depth: 3305 feet

Operator License No.: 33725
Op Name: FOUNDATION ENERGY MANAGEMEN
Address: 14800 LANDMARK BLVD STE 220
DALLAS, TX 75254

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	201		140 SX
PROD 5		3305		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/18/2011 12:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: KENT STRUBE Company: _____ Phone: (620) 786-4161

Proposed
Plugging
Method:

ACCORDING TO KCC RECOMMENDATION.

RECEIVED
JUN 03 2011
KCC WICHITA

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/21/2011 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

RAN TUBING INTO 3250' SPOTTED 35 SX PLUG OF CEMENT WITH CC' PULLED TUBING OUT, TAGGED TOP OF CEMENT AT 2300'. LOG TRUCK RAN WIRELINE IN AND PERFED AT 1150' & 800' & 251'. RAN TUBING BACK TO 1150' SPOTTED 35 SX OF CEMENT, PULLED TUBING TO 800' SPOTTED 35 SX OF CEMENT, PULLED TUBING TO 251' AND CIRCULATED TO SURFACE WITH 190 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3292	3298		

Remarks: COPELAND OUT OF GREAT BEND WAS CEMENT CO. TICKET #36957--LOG TECH PERF TICKET #0785

Plugged through: TBG

District: 02

Signed B. J. Hope
(TECHNICIAN)

JK