

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-21297-00-00  
Spot: NWSESESW Sec/Twnshp/Rge: 34-21S-2W  
656 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: GRABER A Well #: 1  
County: MCPHERSON Total Vertical Depth: 3200 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comments   |
|--------|-------|------------|-------------|------------|
| SURF   | 8.625 | 241        |             | 140 SX CMT |
| PROD   | 4.5   | 3169       | 725         | 75 SX CMT  |

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2011 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: TRAVIS HAMM Company: \_\_\_\_\_ Phone: (620) 755-2461

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/25/2011 9:30 AM KCC Agent: SHANE JONES

Actual Plugging Report:


5/18/2011 KELSO'S DROPPED SAND AND TAGGED IT @ 2980' CAPPED W/4 SX. THEY PULLED STRETCH IN 4 1/2" AND RIPPED PIPE @ 725'. THEY PULLED UP TO 410'. 5/23/11 COPELAND TIED ON AND PUMPED A 160 SX HOT PLUG. KELSO'S PULLED THE REST OF THE 4 1/2" AND RIGGED DOWN. COPELAND WILL COME BACK AT A LATER TIME AND TOP OFF WELL WITH POLY TRAILER. TK #37685 160 SX 60/40 POS W/4% GEL, 3SX CC & 4 SX HULLS. 5/25/11 COPELAND RAN POLY DOWN AND TAGGED @ 135'. THEY CIRCULATED CEMENT TO SURFACE. TK #37688 78 SX 60/40 POS W/4% GEL. I CHECKED TOP PLUG IN THE AFTERNOON STILL AT SURFACE.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3062 | 3070 |      | CSG      |

Remarks:  
Plugged through: CSG

District: 02

Signed  (TECHNICIAN)

RECEIVED  
JUN 06 2011

Form CP-2/3

KCC WICHITA