

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20746-00-00  
Spot: N2NWSE Sec/Twnshp/Rge: 1-14S-15W  
2115 feet from S Section Line, 1985 feet from E Section Line  
Lease Name: DUMLER Well #: 2  
County: RUSSELL Total Vertical Depth: 3370 feet

Operator License No.: 31431  
Op Name: BARTON EXPLORATION, INC.  
Address: 3017 E 14TH ST  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	204	0	w/135 sxs cmt
PROD	4.5	3369	0	w/100 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/06/2011 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: LONNIE BARTON Company: BARTON EXPLORATION, INC. Phone: (785) 650-0541

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Perf: 1200'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/06/2011 10:30 AM KCC Agent: RAY DINKEL

**Actual Plugging Report:**

Ran tubing to 3300' - pumped 75 sxs cement with 100# hulls.  
Pulled tubing to 2100' - pumped 100 sxs cement with 100# hulls.  
Pulled tubing to 600' - pumped 40 sxs cement - cement circulated.  
POOH. Topped off with 7 sxs cement.  
Braden head was dug out and was full of cement.

**Perfs:**

Top	Bot	Thru	Comments
3301			GORHAM SAND
2982			LKC

Remarks: QUALITY CEMENTING COMPANY-TICKET #5020.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED

JUN 17 2011

Form CP-2/3

7/08

KCC WICHITA

JUN 15 2011