

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-19311-00-01  
Spot: SESWNW Sec/Twnshp/Rge: 32-15S-12W  
2984 feet from S Section Line, 4392 feet from E Section Line  
Lease Name: NEY UNIT Well #: 1  
County: RUSSELL Total Vertical Depth: 3410 feet

Operator License No.: 6569  
Op Name: CARMEN SCHMITT, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

| String | Size  | Depth (ft) | Pulled (ft) | Comments      |
|--------|-------|------------|-------------|---------------|
| SURF   | 8.625 | 214        | 0           | w/150 sxs cmt |
| PROD   | 5.5   | 3377       | 0           | w/125 sxs cmt |

Well Type: EOR UIC Docket No: E15052.2 Date/Time to Plug: 06/20/2011 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITCHMAN Company: CARMEN SCHMITT, INC. Phone: (620) 793-5100

Proposed 06/20/2011 - Ordered 450 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Plugging 06/21/2011 - Ordered 400 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Method: Tubing parted at 1368' and casing shifted.  
Tried washing over tubing - could not get down - ran a mill shoe in - got hung up.  
1504' of tubing and AD-1 tension packer left in well.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/21/2011 9:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

06/20/2011 - Ran tubing to 1368' - pumped 75 sxs cement - followed with 100 sxs cement with 450# hulls.  
Little to no blow on the back side.  
Pulled ten joints of tubing - shut down - WOC one hour  
Ran tubing to 1215' - pumped 50 sxs cement with 150# hulls.  
Casing on vacuum - WOC two hours.  
Ran tubing back to 1215' - pumped 100 sxs cement with 3% c.c. and 150# hulls.  
Got 75 sxs in and backside went on a vacuum.  
POOH. Shut down for the night.  
06/21/2011 - Ran tubing and tagged at 814'.  
Pulled tubing to 794' - pumped 90 sxs cement with 200# hulls - cement circulated.  
POOH. Topped off with 5 sxs cement.  
Hooked up Braden head and pumped 35 sxs cement at 150# P.S.I. Shut in.

Perfs:

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #36760.

Plugged through: TBG

District: 04

Signed

R. A. D. K. E. D.

(TECHNICIAN)

CM

JUN 22 2011

RECEIVED  
JUN 27 2011  
KCC WICHITA  
cc to MIC 7/6  
7/6  
Form CP-2/3