

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 4058  
Name: American Warrior  
Address 1: P.O. Box 399  
Address 2: \_\_\_\_\_  
City: Garden City State: KS Zip: 67846 + \_\_\_\_\_  
Contact Person: Kevin Wiles  
Phone: (620) 275-2963  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 5882 Bottom: 5896 T.D. 6272  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 033-21,072 00 00  
Spot Description: C-SE-NW  
C SE NW Sec. 17 Twp. 33 S. R. 18  East  West  
2,120 Feet from  North /  South Line of Section  
2,100 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Comanche  
Lease Name: Lytle Well #: 1-17  
Date Well Completed: 4/24/2000  
The plugging proposal was approved on: 12/23/2009 (Date)  
by: Jerry Stapleton (KCC District Agent's Name)  
Plugging Commenced: 12/28/2009  
Plugging Completed: 12/30/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Production	5 1/2	6055	2500
		Surface	8 5/8	620	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set cast iron bridge plug at 5830', spot 2 sx on bridge plug with dump bailer, lay down 2500' of 5 1/2 casing, run tubing in to 1st 1050', pump 15 sx gel, 50' sx 60/40 poz 4%, 2nd 650' 50 sx cement, 3rd 300' 40 sx cement, 4th 60' 20 sx, circulate to surface.  
12/31 - Measure in, down 12' in surface

RECEIVED  
JAN 08 2010

Plugging Contractor License #: 5105 Name: Clarke Corporation **KCC WICHITA**  
Address 1: 107 W. Fowler Address 2: P.O. Box 187  
City: Medicine Lodge State: Kansas Zip: 67104 + \_\_\_\_\_  
Phone: (620) 886-5665

Name of Party Responsible for Plugging Fees: American Warrior  
State of Kansas County, Barber, ss.  
Mark Morgenstern  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Morgenstern