

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 5123 Name: Pickrell Drilling Company, Inc Address 1: 100 S. Main, Suite 505 Address 2: City: Wichita State: KS Zip: 67202 Contact Person: Jack Gurley Phone: (316) 262-8427 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Morrow Depth to Top: 5307 Bottom: 5349 T.D. 5450

API No. 15 - 057-20152-0000 Spot Description: GZNESE Sec. 32 Twp. 29 S. R. 22 East West 1.980 Feet from North South Line of Section 5.10 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Ford Lease Name: Edmonston "B" Well #: 1 Date Well Completed: 02-02-80 The plugging proposal was approved on: 01-04-2010 by: Eric MacLaran (KCC District Agent's Name) Plugging Commenced: 01-04-2010 Plugging Completed: 01-04-2010

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Includes a 'RECEIVED' stamp from the Conservation Division, Wichita, KS, dated JAN 13 2010.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing the cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

May, 1995, repaired casing leak @ 490' w/ 125 sx. 60/40 Poz plus 50 sx. Common. Circ. cement and squeezed to 750#. Jan. 4, 2010, spotted 25 sx. 60/40 Poz 4% gel w/ 75# cottonseed hulls through tubing @ 5280'. Pulled bottom of tubing to 1500' and circulated cement to surface w/ 100 sx. 60/40 Poz 4% gel. POOH w/ tubing. Topped off casing w/ 15 sx. Pressured 8 5/8 x 4 1/2 annulus to 500#. Held OK. Swift ticket #16684.

Plugging Contractor License #: KLN 32382 Name: Swift Services Inc. Address 1: P.O. Box 466 Address 2: City: Ness City State: KS Zip: 67560 Phone: (785) 798-2300 Name of Party Responsible for Plugging Fees: Pickrell Drilling Company, Inc. State of Kansas County: Sedgwick ss. Jack Gurley (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jack Gurley (Handwritten signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202