

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5447  
Name: Oxy USA, Inc  
Address 1: P.O. Box 2528  
Address 2: \_\_\_\_\_  
City: Liberal State: KS Zip: 67905  
Contact Person: Kenny Andrews  
Phone: (620) 629 4200  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Morrow Depth to Top: 5446 Bottom: 5458 T.D. 5939  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 129-21077 00 - 00  
Spot Description: NE NW  
\_\_\_\_\_  
\_\_\_\_\_  
Sec. 6 Twp. 32 S. R. 39  East  West  
660 Feet from  North /  South Line of Section  
1980 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Morton  
Lease Name: Drew B Well #: 1  
Date Well Completed: 11-2-91  
The plugging proposal was approved on: 12-3-09 (Date)  
by: Mike Meier (KCC District Agent's Name)  
Plugging Commenced: 12-4-09  
Plugging Completed: 12-4-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			20	36	— RECEIVED
			8 5/8	1721	—
			5 1/2	5939	— JAN 13 2010
					KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 300 lb. hulls & 25 sx cmt. to plug perfs from 5446 to 5246, pumped mud spacer to 1800, mixed 25 sx plug from 1800 to 1600, pumped mud spacer to 500, mixed 60 sx plug 500 to 0. Mixed 10 sx plug down annulus from 60 to 0. Cut off 8 5/8 & 5 1/2 & capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent & Horton Plugging Inc.  
Address 1: Rt 1 Box 49 BA Address 2: \_\_\_\_\_  
City: Tyrone State: OK Zip: 73951 + 9731  
Phone: (580) 854 6515

Name of Party Responsible for Plugging Fee: Oxy USA Inc 1701 N Kansas P.O. Box 2528 Liberal, KS 67905  
State of Kansas County, Seward, ss.  
Kenny Andrews  Employee of Operator or  Operator on above-described well  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature]