

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-9-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5447
Name: Oxy USA, Inc
Address 1: P.O. Box 2528
Address 2: _____
City: Liberal State: KS Zip: 67905+
Contact Person: Kenny Andrews
Phone: (620) 629 4200
Type of Well: (Check one) Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
K.L. Munton Depth to Top: _____ Bottom: _____ T.D. _____
K.L. Munton Depth to Top: 4679 Bottom: 4814 T.D. 5725
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 175-21585 00-02
Spot Description: N/2 NE NE
E2 NW NE NE Sec. 5 Twp. 31 S. R. 34 East West
330 Feet from North / South Line of Section
880 Feet from East / West Line of Section
Footage Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Seward
Lease Name: MLP Young Trust B Well #: 2
Date Well Completed: 5-22-01
The plugging proposal was approved on: 12-10-09 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 12-11-09
Plugging Completed: 12-14-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8 5/8	1607	—
			5 1/2	5725	—

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing the cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Load hole w/mud. Weatherford set CIBP + 2 sx cnt. from 4050 to 4035. Stretch showed 5 1/2 stuck below 500. Shot 5 1/2 @ 560 but would not pull. Ran 2 3/8 to 1700. Mixed 25 sx plug 1700 to 1500. Mixed 70 sx 600 to 0. Mixed 5 sx down annulus from 30 to 0. Cut off 8 5/8 + 5 1/2 + capped 8 5/8 5 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc.
Address 1: Rt 1 Box 49 BA Address 2: _____
City: Tyrone State: OK Zip: 73951 + 9731
Phone: (580) 854 6515

Name of Party Responsible for Plugging Fees: Oxy USA Inc 1701 N. Kansas PO Box 2528 Liberal, KS, 67905
State of Kansas County, Seward, ss.
Kenny Andrews (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: _____

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 18 2010
1-13-10
CONSERVATION DIVISION
WICHITA, KS

DR