

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31134
Name: Armor Petroleum, Inc.
Address 1: P.O. Box 4625
Address 2: _____
City: Wichita Falls State: TX Zip: 76308 + 0625
Contact Person: Jerry Arthur
Phone: (940) 692-5001 ext 17
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Morrow Depth to Top: 6114' Bottom: 6132' T.D. 6219'
Chester Depth to Top: 6020' Bottom: 6039' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 119-10260 00 00
Spot Description: _____
_____C_NE Sec. 23 Twp. 34 S. R. 27 East West
1,220 Feet from North / South Line of Section
1,320 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Meade
Lease Name: Merkle Well #: 1
Date Well Completed: 9/10/1960
The plugging proposal was approved on: 12/29/2009 (Date)
by: Steve Durant (KCC District Agent's Name)
Plugging Commenced: 12/29/2009
Plugging Completed: 1/04/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Chester	Gas	Surface	8 5/8"	1400'	None
Morrow	Gas	Production	5 1/2"	6219'	2171'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Load csg w/ mud & set 5 1/2" 10K CIBP @ 5970', cap w/ 2 sks cement . Cut & pull 66 jts 5 1/2" csg from 2171' . Run tbg @ 1450' , mix & pump 100 sks Class "C" cement @ 14.8 ppg w/ 1.32 yield up to 1030' . Pull tbg up to 550' , mix & pump 40 sks Class "C" cement up to 400' , (Did not circulate) WOC 2 hrs , Tag TOC @ 414' , Top out w/ 2 jts tbg 62' - 4' w/ 15 sks cement .

RECEIVED

JAN 14 2010

Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc. **KCC WICHITA**

Address 1: P.O. Box 1707 Address 2: _____

City: Duncan State: OK Zip: 73534 + 1706

Phone: (580) 467-0258

Name of Party Responsible for Plugging Fees: Armor Petroleum, Inc.

State of Texas County, Wichita, ss.

Sherry L. Fitts Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God

Signature: _____