

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34318  
Name: Berexco, L.L.C.  
Address 1: P. O. Box 723  
Address 2: 2020 N Bramblewood, Wichita KS 67201  
City: Hays State: KS Zip: 67601  
Contact Person: Dennis Kirmer  
Phone: ( 785 ) 628-6101  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Topeka Depth to Top: 2810 Bottom: 3006 T.D. \_\_\_\_\_  
Toronto Depth to Top: 3048 Bottom: 3050 T.D. \_\_\_\_\_  
L-KC Depth to Top: 3085 Bottom: 3168 T.D. \_\_\_\_\_  
Arbuckle 3419 3426 3426

API No. 15 - 167.19238.00.00 **KCC**  
Spot Description: W/2 NW SE Sec. 9 Twp. 11 S. R. 15  East  West  
1,980 Feet from  North /  South Line of Section  
2,310 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Russell  
Lease Name: Lebow Well #: 8X  
Date Well Completed: 2-11-63  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Plugging Commenced: 6-6-11  
Plugging Completed: 6-6-11

Show depth and thickness of all water, oil and gas formations.

Oil Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Plugged Out
Topeka	Oil	Surface	8 5/8	225	
Toronto	Oil	Production	4 1/2	3419	
L-KC	Oil				
Arbuckle	Oil				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up Perf Tech. Shoot two holes each at 550, 950, 450, 175. Run open end tubing to 2790. Rig up Allied Cementing. Spot 80 sxs 60/40 poz 4% gel w 300# hulls. P7II tubing to 1565. Spot 75 sxs cement w/200# hulls. Pull tubing to 500'. Circulate cement to surface in 4 1/2 casing. PULL tubing out of hole. Hook up to 4 1/2 casing. Circ cement to surface in 8 5/8 casing w/45 sxs cement. Hole stayed full. Well plugged 3:00 p.m. Witnessed by Ray Dinkel - Hays KCC.

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.  
Address 1: P. O. Box 723 Address 2: 2020 N Bramblewood, Wichita KS 67201  
City: Hays State: KS Zip: 67601  
Phone: ( 785 ) 628-6101  
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.  
State of Kansas County, Sedgwick, ss.  
Dennis Kirmer  Employee of Operator or  Operator on above-described well.  
(Print Name)

**RECEIVED**  
**JUL 07 2011**

**KCC WICHITA**

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Dennis Kirmer

**44**