

R

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG - 8 1979

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -167 -21, 327-00-00 (CONSERVATION DIVISION)
Wichita, Kansas

Operator's Full Name Davies & Co.

Complete Address 1304 Philtower Bldg. Tulsa Okla.

Lease Name Willis D. Anschutz Well No. 1*19

Location C S/2 NE Sec. 18 Twp. 14 Rge. 11 ~~(E)~~ (W) X

County Russell Total Depth 2350'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor B & B Drlg. Inc. & Allied Cementing Co.

Address 515 Union Center Wichita, Kansas 67202 License No.

Operation Completed: Hour 6:30 PM Day 4 Month 8 Year 1979

The above well was plugged as follows:

Filled hole with mud and spotted 50 sx cement at 450'.

Filled hole with mud and spotted 25 sx cement at 270'.

Filled hole with mud to 40' and $\frac{1}{2}$ sx hulls, plug, and
10 sx cement to bottom of celler.

2 sx cement in rat hole.

293' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:
Well Plugging Supervisor

DATE 8-8-79

INV. NO. 0165-W